





## CORRIGENDUM - I

**NAME OF THE WORKS: PROPOSED CONSTRUCTION OF TELANGANA GRAMEENA BANK HEAD OFFICE BUILDING (TWO CELLARS + STILT FLOOR + FIVE UPPER FLOORS) ON BANKS OWN PLOT SITUATED IN SY NO. 417 AND 420, PLOT NO.79, UPPAL BHAGAYATH LAYOUT, UPPAL, HYDERABAD, TELANGANA.**

BOQ		
S.No	Previous Specification	Revised Specification
5	<p><b>CONCRETE WORKS</b> <b>PREAMBLE:</b> The use of admixture, GGBS &amp; crush sand should be as per concrete mix design.</p>	<p><b>SHOULD BE READ AS:</b> The use of admixture &amp; GGBS should be as per concrete design mix as suggested and approved by the Architect and Structural Engineer.</p>
5.1	<p><b>PCC-WORKS (PCC: Volumetric Machine Mix) :</b> Providing and laying in position machine mix PCC (plain cement concrete) under foundation, plinth protection, grade and VDF slabs, coping, sill concrete etc. including transporting, laying, compacting, finishing the surface in line, level and plumb as per requirement and curing etc. complete as per drawings, specifications and as directed by Architect / Bank's Engineer. The rate shall be inclusive of all the material, labour, hardware, transportation, Form work including lead and lift of the material, necessary required for the complete execution of the item as directed by the Architect / Bank's Engineer. <b>Approved make for Cement : ULTRATECH, ACC, RAMCO, INDIA, AMBUJA</b></p>	<p><b>PCC-WORKS (PCC: Volumetric Machine Mix) :</b> Providing and laying in position machine mix PCC (plain cement concrete) under foundation, plinth protection, grade and VDF slabs, coping, sill concrete etc. including transporting, laying, compacting, finishing the surface in line, level and plumb as per requirement and curing etc. complete as per drawings, specifications and as directed by Architect / Bank's Engineer. The rate shall be inclusive of all the material, labour, hardware, transportation, Form work including lead and lift of the material, necessary required for the complete execution of the item as directed by the Architect / Bank's Engineer. <b>Approved make for Cement : ULTRATECH, ACC, RAMCO, INDIA, AMBUJA, NAGARJUNA.</b></p>
7	<p><b>BRICK WORK :</b></p>	
7.1	<p><b>230MM THK BRICK WORK :</b> Providing and constructing Brick masonry walls Using Cement Mortar 1:4 in Superstructure using locally available approved quality Bricks, well (Kiln/Chimney) burnt, uniform size and colour having average crushing strength not less than 50 kg/cm<sup>2</sup> for walls, shaft walls, parapets, drains, manholes, trenches and any other construction elements etc. in proper line, level and plumb including striking out / raking out joints, curing as per IS standards, necessary scaffolding, etc. complete at all heights and levels as per the approved drawings and as per instructions of the Architect / Bank's Engineer. (For all the external walls scaffolding should be used mandatorily. Rate shall be deducted accordingly if not used) The rate shall be inclusive of all the material , labour, hardware, transportation, Scaffolding necessary required for the complete execution of the item as directed by the Architect / Bank's</p>	<p>Specification stands the same.</p>

	<p>Engineer.  <b>Rate should be quoted considering execution of work in Sub cellar, Cellar, Stilt + 5+Head rooms on Terrace floor.</b></p>	
<p>7.2</p>	<p><b>115MM THK BRICK WORK FOR INTERNAL WALLS :</b>          Providing and constructing half-brick masonry partition walls Using Cement Mortar 1:4 in Superstructure using locally available approved quality Bricks, well (Kiln/Chimney) burnt, uniform size and colour having average crushing strength not less than 50 kg/cm<sup>2</sup> for walls, shaft walls, parapets, drains, manholes, trenches and any other construction elements etc . The walls shall includes providing RCC patti beam 100mm thick including providing with 4 nos. 8 mm dia TMT bars and 8 mm dia TMT links at 300 c/c in cement concrete of mix M 20 at mid-height at every 900mm height, required formwork etc. in proper line, level and plumb including striking out / raking out joints, curing as per IS standards, necessary scaffolding, etc. complete at all heights and levels as per the approved drawings and as per instructions of the Architect / Bank's Engineer. The rate shall be inclusive of all the material ,labour, hardware, transportation, Scaffolding necessary required for the complete execution of the item as directed by the Architect / Bank's Engineer.  <b>Rate should be quoted considering execution of work in Sub cellar, Cellar, Stilt + 5+Head rooms on Terrace floor.</b></p>	<p>Specification stands the same.</p>
<p><b>Note: All other Tender Terms, Conditions and Specifications remain same.</b></p>		

<p><b>Signature's</b></p>	
 <p>The General Manager-Operations</p>	
 <p>E.SREENATH          architect urban planner          CA/2000/26267          AITP-2004-013</p>  <p>M/S Abhikram-s architects.</p>	